BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 61

Name of Work:-Improvements of roads and drains in A sector in ward no:04 Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2015-16)	Cum	184.77	83.00	Rupees eighty thtee only
2	Removing B.S slab of drain and stacking (P.No 25 I.No 5.32)g	sqm	935.55	63.00	Rupees sixty three only
3	Refixing stone slabs of drains and pointing in CM(1:3)(P.No 25 I.No 5.33)	sqm	935.55	78.00	Rupees seventy eight only
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms	sqm	400.95	600.00	Rupees six hundred only
5	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2015-16	Cum	184.77	68.00	Rupees sixty eight only
6	KSRRBM400-17,Providing, laying, spreading andcompacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site,laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired dencity complete as per specifications.MORTH Specification No.406(Item no20.18,Page no157 ,PWD SR 205-16)	Cum	101.00	1710.00	Rupees one thousand seven hundred ten only
7	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH Specifications No502	sqm	2657.50	31.00	Rupees thirty one only

Chief Accounts Officer

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri B P MAHESH	
				Rate	Rate in Words
8	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and alignment,rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethedesiredcompactionasperMORTHSpecificationclauseno508completeinallrespectscompleteasperspecifications.using100120THcapacityH.M.P with sensor paver grading (35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2015-16)	Cum	85.50	9261.00	Rupees nine thousand two hundred sixty one only
9	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications. Specification no KBS4.1,4.2	Cum	4.55	5070.00	Rupees five thousand seventy only
10	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2015-16,p.no13, no4.11)	Cum	15.83	6099.50	Rupees six thousand ninety nine and paise fifty only
11	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2015-16,p.no17,s.no4.46)	Qtl	6.11	6899.00	Rupees six thousand eight hundred ninety nine only
12	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2	Sqm	17.70	300.00	Rupees three hundred only
13	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No 23, I.No 5.60)	Cum	11.95	4000.00	Rupees four thousand ony

B.P. Mahesh

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64